

Project Profile

Lubes Terminal Demolition – Stage 1



Client	Oil Industry Leader
Location	Wellington, North Island, New Zealand
Duration	October 2017 to February 2018
Contract	Lump Sum Construct Only
Cost	Confidential

Project Overview

An oil industry leading company required demolition, asbestos and hazardous waste remediation and scrap metal services for nominated structures within an operational petrochemical terminal near Wellington, New Zealand. Scope of works included the removal and remediation of ten aboveground storage tanks, buildings and associated pipe work, the removal of hydrocarbons and asbestos removal and appropriate treatment which included galbestos, gaskets and cement sheeting.

Works were undertaken adjacent to operating terminal facilities requiring stringent adherence to the client's loss prevention system and clear delineation of demolition zones from operational zones. Permanent fencing separating the work site from a major road had geotextile fabric attached to alleviate dust mitigation from the work site.

Over 27t of asbestos waste and 1800m² of asbestos sheeting was removed and appropriate remediated offsite and licenced receiving stations. 695t of steel was scrapped and recycled.

McMahon Services

Head Office

T (08) 8203 3100 F (08) 8260 5210

E adelaide@mcmservices.com.au

W mcmservices.com.au





McMahon Services

Head Office

T (08) 8203 3100 **F** (08) 8260 5210

E adelaide@mcmahonservices.com.au

W mcmahonservices.com.au

